NO.-BDG-1288/A.NO.-36, DESK-BUILDING-I, DATED 25-05-1989.AND WORKING DRAWINGS ARE PREPARED BY THE CHIEF ARCHITECT, M.S. MUMBAI VIDE JOB NO. T-EDU-5213/II, DRG. NO.- 01 TO 04

NOTES :

1. ALL DIMENSIONS ARE IN METERS UNLESS MENTIONED OTHERWISE.
2. ANY DISCREPANCY NOTICED IN THIS DRAWING SHALL BE COMMUNICATED TO THIS OFFICE BEFORE EXECUTION OF THE WORK.
3. THE FINISHED FLOOR LEVELS OF TOILETS SHALL BE SUNKED BY 15mm THAN GENERAL FINISHED FLOOR LEVEL.
4. ORRISA PATTERN W.C. PAN SHALL BE PROVIDED IN ALL W.C.S. EXCEPT PRINCIPAL'S ATTACHED TOILET & HANDICAPPED TOILET. PROVIDE U ROPEAN W.C. PAN
5. THIS DRAWING SUPERSIDS ALL OTHER DRAWINGS BEARING JOB NO.- T-EDU/5213/II, DRG.NO. 1,2,3,4.
6. THE INTERNAL LAYOUTS SHOWING PLATFORMS, BLACKBOARDS, DIAS, CHANNELS, ETC. ARE INDICATING ONLY FOR ESTIMATE PURPOSE & ARE SHOWN ON THE BASIS OF 'LAY OUT' IN THE REPORT OF HEDADQ COMMITTEE TYPE PLAN COMMITTEE PAGES 176 TO 205. FOR CONSTRUCTION PURPOSE REFER SEPARATE DETAILS.

PT-PLATFORM WITH ONE SIDE POLISHED KADDAPA TOP AND 80 cm C/C 15 cm THK. BRICKS WALL SUPPORTS AS PER DETAIL

BB-BLACKBOARD SIZE 6·0 X 2·0 X 0·30 m HT MADE FROM FLEXO-O-BOARD OR SIMILAR MATERIAL

RK-BUILT IN RACKS WITH ONE SIDE POLISHED KADDAPA STONE SLAB SHELVES IN 6 TIER 35 cm C/C AS PER DETAIL

APPROVAL NOTE :

THIS WORKING DRAWING IS PREPARED ON THE BASIS OF LINE PLANS APPROVED BY DIRECTOR, TECHNICAL EDUCATION, MAHARASHTRA STATE , MUMBAI AND THIS APPROVAL IS CONVEYED BY EXECUTIVE ENGINEER P.W.D. (R.P.), JALGAON, VIDE HIS LETTER NO R.P.DIV./ ADM-2/513/2004, DATED 25-05-2004

S.NO	DATE	SIGN	CONTENTS
REVISION			

COUNTER SIGNATURE

P.C. BANSODE CA/75/5352
CHIEF ARCHITECT
M.S. MUMBAI.

OFFICE OF THE
DY. CHIEF ARCHITECT
P. W. REGION
AURANGABAD.

P.S. BALIWANT CA/80/7574
DY. CHIEF ARCHITECT

PROPOSED MODIFIED PLAN OF ACADEMIC BUILDING FOR GOVT. ENGINEERING COLLEGE AT JALGAON.

WORKING DRG.
{ GROUND FLOOR PLAN. }

1 : 100	25/05/04.	MACPANCHGALLE S.R.KHANORE
SCALE	DATE	DEALT BY
JOB NO. JLG(4)9/77		DRG. NO. 06

GROUND FLOOR PLAN
SCALE - 1:100